

DOE-OE Energy Storage Technology Advancement Partnership (ESTAP) Webinar

Commissioning an Energy Storage System: Lessons Learned in the Field

September 7, 2022



U.S. DEPARTMENT OF
ENERGY




Sandia
National
Laboratories



CleanEnergy
States Alliance

Webinar Logistics



Join audio:

- Choose Mic & Speakers to use VoIP
- Choose Telephone and dial using the information provided

Use the orange arrow to open and close your control panel

Submit questions and comments via the Questions panel

This webinar is being recorded. We will email you a webinar recording 48 hours. This webinar will be posted on CESA's website at www.cesa.org/webinars

CleanEnergy States Alliance



Governor's Energy Office




Maryland Energy Administration



MICHIGAN DEPARTMENT OF ENVIRONMENT, GREAT LAKES, AND ENERGY



Washington State Department of Commerce




DOE-OE Energy Storage Technology Advancement Partnership

The **Energy Storage Technology Advancement Partnership (ESTAP)** is a US DOE-OE funded federal/state partnership project conducted under contract with Sandia National Laboratories.


ESTAP Key Activities:

1. Facilitate public/private partnerships to support joint federal/state energy storage demonstration project deployment
2. Disseminate information to stakeholders
 - ESTAP listserv >5,000 members
 - Webinars, conferences, information updates, surveys.
3. Support state energy storage efforts with technical, policy and program assistance



ESTAP Project Locations

Thank You!



Dr. Imre Gyuk

Director, Energy Storage Research,
U.S. Department of Energy



Dan Borneo

Engineering Project/Program Lead,
Sandia National Laboratories



Webinar Speakers



Dr. Imre Gyuk

Director of Energy Storage Research,
DOE Office of Electricity



Dan Borneo

Engineering Project/Program Lead,
Sandia National Laboratories



Dave Galarowicz

Lead Engineer,
Alliant Energy



Clay Koplin

CEO, Cordova Electric Cooperative



Todd Olinsky-Paul


Senior Project Director, Clean Energy States Alliance (moderator)



Commissioning an Energy Storage System: Lessons Learned from the Field



ESTAP Webinar Series
September 7, 2022



PRESENTED BY **Dan Borneo – Sandia**
Susan Schoenung – Longitude 122 West

SAND2022-11761 PE




Sandia National Laboratories is a multimission laboratory managed and operated by National Technology & Engineering Solutions of Sandia, LLC, a wholly owned subsidiary of Honeywell International Inc., for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525.

Sandia team and 2021-22 DOE-OE Sponsored Projects





State or Territory	Partner
Alaska	Cordova Electrical Cooperative (CEC)
Alaska	Alaska Village Electrical Cooperative (AVEC)
Arizona (x3)	Navajo Tribal Utility Authority (NTUA)
Colorado	Poudre Valley Rural Electrical Association (PVREA)
Florida (x4)	Seminole Tribe
Hawaii	Natural Energy Laboratory of HI Authority (NELHA)
Iowa	Alliant Energy
New Mexico	Santa Fe Community College
New Mexico	Albuquerque Public Schools




State or Territory	Partner
New Mexico	Picuris Tribe
North Carolina	NC Electric Membership Corporation (NCEMC)
North Carolina	Ft. Bragg Sandhills Utility Services (SUS)
Puerto Rico	Villalba Municipality
South Dakota	Ellsworth AFB West River Electric Association (WREA)
Tennessee	Electric Power Board of Chattanooga (EPB)
Vermont	Green Mountain Power (GMP)

Energy storage system overview (ES is one Part of Whole)






Commissioning begins with RFP



The Project Team includes



Involvement with commissioning

Team Member	Project Responsibility
Owner 	Programming, Financing, contracting and ownership strategies. Developer or Facility
Design Engineer 	Design, Load profile, application(s), codes/standards/specifications, Procurement RFP, Inspection,
Utility 	Interconnection authorization, Point of connection work
Site Construction team/installer 	EHS / Site Safety Plans (SSP) and Safety Meetings, Site prep, permits, system delivery, Construction, all BoP
Vendor 	Factory Witness Testing, Shop drawings, On-site connections, start-up, troubleshooting, Warranty
AHJ	Code adherence, Design verification
System integrator, or Commissioning Agent 	OWNS COMMISSIONING. Plan, Construction inspection, Operational Acceptance Testing (OAT), Integrated System Startup (S/U), Functional Acceptance Testing (FAT), shakedown, Training, as-builds, Commissioning Closeout
Fire Department	Design review, Participate in training

Codes and Standards Related to Energy Storage Installations (*beware of new requirements*)



Standards and Model Codes Hierarchy



Acceptance Testing is the heart of Commissioning




Figure 3. Commissioning process steps

https://www.sandia.gov/app/uploads/sites/163/2021/09/ESHB_Ch21_Commissioning_Schoenung.pdf

Acceptance Testing of ES Components and Subsystems



Battery/DC Block:

- Rack, module, cell level data
 - Temperatures
- Calculated values
 - SOC, SOH

Power Conversion:


- Inverter data (individual & aggregate)
 - DC voltage, current
 - AC voltage, current, frequency, power factor
- Calculated values

Applications

- Utilize SOO

Balance of Plant (Environment, Safety Systems):

- Enclosure data:
 - Temperature, humidity
 - IR scan
- Local data
 - Outside temperature, humidity
- Fire Protection
 - Water and/or dry chem system status
 - Smoke/heat sensors
- Alarms
 - Faults, e-stops, door open, etc.
- Grid (Point of Connection – POC)
 - Voltage, current



Testing procedures

Lessons Learned (It always takes longer than you think)



- Interconnection Request & Approval
 - *It can be a long process – start early, make contact with the Utility, follow through*
- BESS Siting (Location)
 - *Know your installation Standards/Codes consideration*
- Developing a RFP
 - *It is recommend that ‘best practice’ Codes/Standards are used in the RFP (specifically UL9540 2020 & NFPA 855 2020/IFC 2018 or 2021) no matter what Code year the State has adopted.*
 - *Load Profile and Application identification*
- Bid Analysis: Need to understand who is supplying which component of the BESS
 - *Who does what and who is in charge. In most cases there will be multiple vendors suppling different portions of the energy storage system which can lead to confusion about who is responsible for **acceptance testing** of individual components*
- Communications/Data Acquisition
 - *Collecting **ES data for monitoring** can be complex and scales in complexity with the size of the system, number of data points you have/want, frequency, etc. **Get an IT person on-board the project team.***
 - *Cybersecurity of remote monitoring/data collection is a growing concern.*

Lessons Learned (Continued)

- Training of operations and first responders
- IT / data collection – What to measure and does it work
- Fun Facts (unless you are there)
 - Red hot bolts – Not torqued
 - Failed Cables – Not meggered
 - Breakers inadvertently tripping – Not coordinated properly
 - Distribution Equipment Failure – Not installed correctly
 - Over heating - Ventilation not sized correctly
 - Water Leaks – Piping connections not tested
 - Controls - Adequate testing procedure
 - Application – Sequence of Operations (SOO) not well thought out




Questions that Bother Me So

- Who leads Commissioning and how to identify/request in RFP
- What if Equipment is delayed?
- Which State and Federal codes/Standards need to be followed
- What's an interconnection agreement?
- How long will the battery realistically last?
- Predictive measurements of battery to indicate performance?
- Given today's economic environment how realistic are the cost and delivery estimates?



Conclusions

- Commissioning can be described as **PAYING ATTENTION to the DETAILS**
- Energy Storage resources available online
- SNL and EPRI developing updated commissioning guide for year-end release



Thank you



This work is funded by the DOE OE Stationary Energy Storage program, directed by Dr. Imre Gyuk.



Daniel Borneo drborne@sandia.gov

Great project, but...

Commissioning
delayed by difficult access
to vendors for data...

Decorah Battery System Design

- 2.5 MW, 2.9 MWH system

Power (flow rate)

Energy (size of tank)

Duration

$$2.9 \text{ MWH} \div 2.5 \text{ MW} \\ = 1.16 \text{ HRS}$$

- Larger power rating → more flexibility
 - Voltage managed with reactive power (Vars)
 - Power Flows managed with real power (Watts)
- Samsung / Sungrow Integrated Solution from EnelX
 - Lithium Ion (NMC Chemistry)





Commissioning an Energy Storage System

Lessons Learned from the Field
September 7th, 2022

Decorah Design



Decorah Battery Project

Alliant Energy, with EnelX (integrator) and Samsung-Sungrow (Mfr)

Location: Leased Land in City Park - Decorah, IA

What: NMC Li-Ion Battery, 2.5 MW, 2.9 MWH

Why: Increasing Hosting Capacity (Ability to Accommodate DG)

When: RFP issued: Spring 2019

Contract placed: Fall 2019

Installation complete: Summer 2021

Commissioning complete: June 2021


- *Pending Field Certification*
- *Pending Final Fire System Testing*

Turnover and operation

How much:

Total Estimated cost: \$2.9 MM

DOE Cost share (equipment only): \$250,000



Module Installation

Visual Screening



Decorah Commissioning



Post Manufacture Certification

- Corrected labeling of devices and container
- Field certification
 - Long lead times for scheduling of inspectors (>3 months)
 - In progress for water ingress testing

Site Commissioning Actions Taken

- Implemented non-zero power setpoint to minimizing open / close cycles on the DC contactors
- Encountered frequent battery fans failures, which have been replaced
- Animal ingress was addressed early in the design process and has not posed an issue.
- Implemented automated alarms and e-mail notification for loss of communications and availability

Site Commissioning Improvements (1)

- Ensure that EMS can issue reset commands to the BMS / PCS remotely as allowed by BMS manufacturer
- Coordinate with EMS manufacturer to integrate aftermarket off-gas detection systems
- Verify connectivity and system functionality in advance of system performance testing.

Site Commissioning Improvements (2)

- Request commissioning checklist/plan to review and provide feedback
 - Should test operational processes including starts/stops/alarm resets/setpoint tracking
- Test alarms from the field through to SCADA

QUESTIONS?



Presenter



- Dave Galarowicz, P.E.
 - Dave Galarowicz has spent 13 years in the utility sector. He has worked extensively in power generation and fossil units in both engineering and operations roles. He is currently working on pilot scale projects, deploying new technologies to evaluate their value and potential to integrate into the Alliant Energy system.

Procuring and Commissioning an Energy Storage System- Cordova Electric Cooperative



Energy Storage Technology Advancement Partnership (ESTAP)
DOE-OE-ES Clean Energy States Alliance CESA Webinar
September 07, 2022


Cordova, AK (aerial view)

Cordova Electrical Grid

Humpback Creek Hydroelectric Plant
1250kW (2 x 500 kW + 1 x 250 kW)
17 000 foot UG and submarine transmission line



Power Creek Hydroelectric
6278kW (2 x 3124 kW)
25 kV transmission ties to Eyak Substation Inflatable dam



City of Cordova
1 566 customers
18MW
One Substation
78mi UG distribution lines



Battery Energy Storage System
1 MW 1MWh
ABB/SAFT at Eyak Substation



Orca Power Plant
10.8 MW Diesel
Control Center
CEC




Procurement – Start in the Right Place

(Dr. Imre Gyuk Director of Energy Storage Research Office of Electricity)

- US DEPT OF ENERGY-SANDIA-ACEP INITIAL MODELLING TO RIGHT-SIZE
- SANDIA AND NRECA – DRAFT SPECS AND PROCUREMENT DOCS
- CEC INTERNAL SPECS AND INTEGRATION - USE CASE!
- SHARE FINAL DOCS BACK TO NRECA AND SANDIA FOR TRANSFER
- CRITICAL; MEETING OF THE MINDS WITH SAFT/ABB




Office of
ELECTRICITY



A little more detail: Commissioning Planning

- MANUFACTURERS HAVE STANDARD COMMISSIONING PLANS AND PROTOCOLS
- STRUCTURE YOUR COMMISSIONING AROUND YOUR USE CASE AND INTEGRATION
 - Communications Integration – compatible protocols handshaking etc.
 - Controls Integration – serial vs. parallel comms (Modbus TCP vs. Modbus RTU)
 - Operational Integration – “bumpless” state change ramp rates mode transfers



BATTERY – POWER CONVERTER – CEC SCADA SYSTEM HANDSHAKING

CEC Commissioning Docs

Map all I/O – test everything – follow through follow through follow through...

A	B	C	D
	Customer Site Acceptance Steps	Notes	Date Tested
1	Verify that there are no mechanical defects or physical damage from factory or shipping	Fire Alarm on the Battery was damaged and the air conditioner was dented	6/17/2019
2	Verify all the components that we ordered are present and in good condition	Inventoried upstairs at ORCA	8/24/19
	Power up station service devices (lights, Fans, Fire system, Etc) and ensure they all are working properly	The air conditioner on the battery needed troubleshooting and repair, this was completed by Ed on 6/10/19.	6/10/2019
2	Verify that the fire alarm bypass is working i.e. test it during fire suppression test	NOT A BYPASS! NEED TO VERIFY OPERATION WHEN FIRE ALARM CONTRACTOR IS HERE	
3	Verify that transformer alarms are paralleled onto EYAK PLC I/O card	They are not, THEY ARE POLLED BY PWRC OVER TCP FROM ABB AND DISPLAYED ON SAFT/ABB DETAIL PAGE	Week of 6/18/2019
4	ABB, CEC and SAFT to complete their site integration work	Abb still needs to implement final iteration of soc limit ramping to 0. Emailed after second commissioning trip.	
	Power up control/ comm devices and ensure they all are working properly	A control relay in the PCS e-stop string was faulty upon startup and had to be replaced this was done by Nate and Isak on 6/6/19. Some Ribbon cables from the Master PCS controller to the inverters were not working these were replaced by Nate and Isak and Allen on 6/6-7/19. The MBMM was faulty and needed reprogramming this was done by Ed on 6/8/19 and 6/10/19. The vacuum alarm on the main stepup transformer is faulty and needs to be repaired or replaced. the Master control in the PCS is faulty and needs to be repaired or replaced. The modbus rtu communication from the ABB Plc to the CEC Plc is Very slow (about 1-3 seconds between good reads) and needs to be repaired. the ABB Plc would not communicate at all without using two stop bits. The setting should be one stop bit this needs to be repaired, Sometimes the modbus rtu communication to and from the CEC Plc and ABB Plc will just stop this needs to be repaired. sometimes the communication to and from the ABB plc and Saft plc will just stop. this needs to be repaired.	8/23/2019
4-1			
4-2	Verify Communication settings (ip, programmable switch settings)		Week of 6/18/2019
4-3	Verify communication is working between all CEC, ABB, Saft devices.	Ping all devices	Week of 6/18/2019
5	Verify ramp rates of 10kW/s for all configurable settings	How? Look over Isak's shoulder	Week of 6/18/2019
6	Verify that 15 second trip on loss of comms is disabled, i.e. let the battery ramp when dead or full	Unplug the comms while it is running at 500 kw and watch the ramp. COMM LOSS TRIP IS DISABLED AS OF 8/23, STILL NEED TO SEE SAFT BATTERY SOC PROTECTIVE RAMP	
7	Get modbus alarm register details from saft and abb	Get the location of these per trevers email on 4/28	4/28/2019
8	Additional verifications before CEC ties to their grid.....	Phase Rotation? Breaker Operation? E-stop operation? Protective device settings?	Week of 6/18/2019
9	ABB SAFT team to manually test each register in PCS	CHECK COMMISSIONING DOCUMENT TO SEE IF THIS WAS DONE	
10	Tie BESS to CEC Buss through fused disconnects		Week of 6/18/2019
11	Verify all comm interface registers from Pcs to Eyak are correct		Week of 6/18/2019
12	Verify all comm interface registers from Eyak to Pcs are correct		Week of 6/18/2019
13	Tie to grid		Week of 6/18/2019
	Run system locally from Pcs hmi. Verify each mode, and each setpoint, and confirm it is seen on CEC hmi. Mode Requested 0=Off 2=Csi(Baseload) Charge/Discharge Setpt (-1000 to 1000), Positive = Discharging, Negative = Charging Kvar Setpt (-1000 to 1000) pos = inductive, neg = capacitive 1=Vsi(Isoch) Voltage Setpt - 7000 - 7600	What to do with the system	
14	Frequency Setpoint - 5900 to 6100		
	Put the BAT in off mode on the panel and look at Scada and see if it registers.		
14-1	=yes do nothing. =no troubleshoot and fix it.	Nothing	

Meeting of Minds

(highly recommended)

- High level discussion between project partners and vendors to carefully articulate the use case the operating environment the operating modes and purpose. The discussion pushes on the applications and capabilities of individual components in various operating modes and environments and discusses weather electrical system dynamics communications controls handshaking with SCADA / automation system. All should leave with a clear pictures of the application and a working list of items to test or confirm for the application to minimize the inevitable challenges during installation commissioning and operation





Site Work – May/June 2019











INSTALLATION / COMMISSIONING



July 2019 – Manual Operations Commence

TIMELINES

- ▶ 2007 – CEC System Loads Exceed Hydro Capacity and diesel peaking creates a “valley of death”
- ▶ 2012 – CEC partners with ACEP and recognizes the benefits of energy storage to CEC Grid
- ▶ 2015-16 ACEP Approaches Dr. Gyuk with CEC use case/opportunity and rich CEC data set
- ▶ 2016 Dr. Gyuk initiates phase 1 modelling of CEC energy storage via Sandia Laboratories
- ▶ 2017 Modelling and analysis indicates a right-sized right-located Lithium Ion solution for CEC
- ▶ 2018 Dr. Gyuk sponsors phase 2 specification and procurement of BESS
- ▶ October 2018 CEC BESS Ordered
- ▶ May 2019 BESS arrives on site
- ▶ June 2019 BESS Installed
- ▶ July 2019 BESS Operational
- ▶ November 2019 Fully integrated and automated saves \$10 000 over 2-day Thanksgiving Holiday
- ▶ November CEC achieves 94% hydro crushing all previous records
- ▶ December 2019 CEC achieves 86% hydro crushing all previous records
- ▶ April 2020 CEC goes 100% hydro 3 weeks early and starts automated electric boiler heating
- ▶ 2021: Saved 50 000 gallons of diesel directly with BESS 14 000 gallons indirectly with e-boiler
- ▶ 2022: Delivering more hydro upgraded diesel heat loops to save 25 000 gallons with e-boiler
- ▶ 2022: New valves unleashed more hydro; extending heat loops and EV charging with excess hydro

RIBBON CUTTING June 7 2019



CEC BESS Commissioning – Takeaways

- ▶ Conduct a meeting of minds and document functional items – project teams can change
- ▶ Understand the ecosystem – a microgrid does not have an infinite bus / fault current
- ▶ Make sure vendors close the gap between sales staff and field installers
- ▶ Details matter – bumpless switching between power converter modes was/is challenging
- ▶ Pay attention to alarms – lots of internal alarms may have value to vendor but not the client
- ▶ Pay close attention to warranties and PMs a big challenge in Alaska and a work in progress



Questions?



Webinar Speakers – Q&A

- **Dr. Imre Gyuk**, Director of Energy Storage Research, Office of Electricity, US Department of Energy
- **Dan Borneo**, Engineering Project/Program Lead, Sandia National Laboratories
- **Dave Galarowicz**, Lead Engineer, Alliant Energy
- **Clay Koplín**, CEO, Cordova Electric Cooperative
- **Todd Olinsky-Paul**, Senior Project Director, Clean Energy States Alliance (moderator)



This webinar was presented by the DOE-OE Energy Storage Technology Advancement Partnership (ESTAP)

Dr. Imre Gyuk

US DOE-OE

imre.gyuk@hq.doe.gov

Dan Borneo

Sandia National Laboratories

drborne@sandia.gov

Todd Olinsky-Paul

Clean Energy States Alliance

todd@cleanegroup.org

ESTAP Website: <https://cesa.org/projects/energy-storage-technology-advancement-partnership/>

ESTAP Webinar Archive: <https://cesa.org/projects/energy-storage-technology-advancement-partnership/webinars/>



Upcoming Webinar

Advancing Solar for Manufactured Homes through Community Solar

Wednesday, September 14, 2-3pm ET

Panelists will share more information about how community solar can be used to bring the benefits of solar to manufactured homes; how to engage with the U.S. Department of Energy's National Community Solar Partnership; and successful examples of community solar projects that have benefitted manufactured homes and communities.

Read more and register at: www.cesa.org/webinars

